

कार्य का नाम	: CCTV Camera की आपूर्ति एवं स्थापित करने हेतु दर अनुबन्ध
निविदा कार्य की अवधि	: 03 माह
निविदा शुल्क	: रू. 500/-
धरोहर राशि	: रू. 4000/- (अक्षरे रू. चार हजार मात्र)
निविदा जमा करने की तिथि	: दिनांक: 14/03/17 समय दोपहर 2.00 बजे तक
निविदा खोलने की तिथि	: दिनांक: 14/03/17 समय सायं 3.00 बजे

कुलसचिव
कोटा विश्वविद्यालय, कोटा

निविदा प्रपत्र
(निविदाकार द्वारा भरकर लिफाफे में सीलबंद कर रखने हेतु)

1. निविदा प्रस्तुत करने वाली फर्म का नाम
एवं पता
दूरभाष नम्बर
2. संदर्भ निविदा सूचना क्रमांक
3. निविदा प्रपत्र शुल्क की राशि रेखांकित बैंक ड्राफ्ट संख्या दिनांक:
संलग्न किया जा रहा है।
4. हम कोटा विश्वविद्यालय द्वारा जारी की गई निविदा सूचना संख्या दिनांक:
..... में वर्णित सभी शर्तों से तथा संलग्न शीट में दी गई उक्त निविदा सूचना की अतिरिक्त
शर्तों से बाध्य होना स्वीकार करते हैं। इनके सभी पृष्ठों पर उनमें उल्लेखित शर्तों को हमारे द्वारा
स्वीकार किए जाने के प्रमाण में हमने हस्ताक्षर कर दिए हैं।
5. फर्म द्वारा आदेश प्राप्त करने के दिनांक से 15 (पन्द्रह) दिवस की अवधि के भीतर कार्यादेश में वर्णित
दरों एवं शर्तों के अनुसार कार्य प्रारम्भ किया जावेगा।
6. उद्धृत की गयी दरें दिनांक: से तक एक वर्ष की अवधि के लिये विधि
मान्य है। इस अवधि को पारस्परिक सहमति के आधार पर बढ़ाया भी जा सकता है।
7. सफल बोलीदाता को नियमानुसार प्रतिभूति राशि जमा करानी होगी तथा निर्धारित मूल्य के
मूद्रांक(स्टाम्प)पर अनुबन्ध निष्पादित करना होगा।
8. बोलीदाता द्वारा संलग्न एच-शिड्यूल में आपूर्ति एवं स्थापित करने के कार्य की न्यूनतम दरे भरकर
देनी होगी।

निविदादाता के हस्ताक्षर मय मोहर

UNIVERSITY OF KOTA
M.B.S Marg, Kabir Circle, Kota
H-Schedule
CCTV Details

Sr. No.	Item Description	Qty. (Estimated)	Unit Rate(Rs.)	Total Amount (Rs.)
01	Supply & Installation of 2MP(1080P) HDTVI IR Dome Camera Minimum 1/3" Analog High Definition Sensor , Minimum 25/30FPS@1080P, Minimum 3.6MM Fixed Mega Pixel Lens, Minimum ILLUMINATION ; 0.01 LUX, Auto White Balance, Auto Gain Control Internal Sync, 12V DC±10 Make-Branded with standard certification	08		
02	Supply & Installation of 2 MP (1080P) HDTVI IR Bullet Camera Minimum 1/3" Analog High Definition Sensor , Minimum 25/30FPS@1080P, Minimum 3.6MM Fixed Mega Pixel Lens, Minimum ILLUMINATION ; 0.01 LUX, Auto White Balance, Auto Gain Control Internal Sync, CE, ROHS & FCC Certified , IP66 Weather proof Housing , 12V DC±10% Make-Branded with standard certification	05		
03	12 V, 10A DC Power Supply For IR Cameras Make-Branded with standard certification	05		
04	4U RACK for DVR Setup Make-Branded with standard certification	05		
05	Loose Connection free Molded BNC Connector (2 Nos. for each Camera) Make-Branded with standard certification	13		
06	DC Pin Make-Branded with standard certification	13		
07	Supply & Installation of 08 Channel 1080P Real Time view and DVR with 2CH Audio & TV out 08 CH video, 2 CH audio, Recording Capacity : 1080P Real Time , Full Channel Playback Synchronously, HDMI, VGA, TV Output, Support 1HDD UPTO 4 TB; MINI 1U Casing; USB 2.0" Make-Branded with standard certification	03		
08	Supply & Installation of 04 Channel 1080P Real Time view and DVR with 2CH Audio & TV out 04 CH video, 2 CH audio, Recording Capacity : 1080P Real Time , Full Channel Playback Synchronously, HDMI, VGA, TV Output, Support 1HDD UPTO 4 TB; MINI 1U Casing; USB 2.0" Make-Branded with standard certification	02		
09	2 TB Surveillance Hard Disk Make-Branded with standard certification	05		
10	Supply & Installation of 18.5" Display Monitor Screen Size 18.5 (46.99CMS), Minimum Make-Branded with standard certification	05		

11	CAT-6 Networking Patch Cord – 5Mtr. Make-Branded with standard certification	05		
12	CAT-6 Networking Patch Cord – 1Mtr. Make-Branded with standard certification	05		
13	8 Port Gigabit Switch Eight 10/100/1000 MBPS Gigabit Ports, 16 GBPS Switching Fabric, Auto MDI/MDIX Crossover for all ports, Secure store and forward switching scheme, Full/Half-Duplex for Ethernet/Fast Ethernet Speeds, IEEE 802.3X flow control supports 9000 byte jumbo frames supports IEEE 802.1P QOS (4 queues, strict mode), supports cable diagnostics function , plug-and-play installation ,ROHS compliant Make-Branded with standard certification	01		
14	UPS – 600VA , 360W Make-Branded with standard certification	05		
15	Spike Buster – 4 Socket Make-Branded with standard certification	05		
16	Installation & Commissioning of Complete CCTV system with All Necessary Accessories to complete the CCTV system	01 Lot		
17	Cabling Charges under casing-capping/piping Including pure copper cable & labor cost.	As per running Meter.		

All the item from 1-17 should be branded i.e. vendor should write brand name at the time of submission of tender (Technical as well as financial).

Signature of Tenderer with Rubber Stamp